

2006-2007 Village of Speculator Elm Lake Road



This project consists of design, layout, preparation of contract drawings and specifications, construction administration and observation for the construction of approximately 10,000 feet of sanitary sewer extension including 46 manholes, one submersible pump station and one grinder pump station. Engineering services provided for all phases of the project included:

- ◆ Funding Procurement
- ◆ Preliminary Engineer's Report
- ◆ Conceptual Design and Layout
- ◆ Contract Drawings and Specifications
- ◆ Construction Administration
- ◆ Construction Observation

The major components of the project included:

- ◆ 25' Deep Submersible Pump Station
- ◆ 16' Deep Grinder Pump Station
- ◆ 730' +/- of 4" Force Main
- ◆ 10,000' +/- 8" Gravity Sewer
- ◆ 46 Manholes

Expected construction completion in the spring of 2007.

Reference:

Village of Speculator
Florence Braunius, WWTP Operator
PO Box 396
Speculator, NY 12164
(518) 548-7354